

justin.wiser@cwroofingservices.com

Property: 4219 Texana Dr
Baytown, TX 77523

Estimator: ScopeConnect

E-mail: scopeconnect@claim-connection.com

Contractor:
Company: CW Roofing & Construction

E-mail: justin.wiser@cwroofingservices.com

Claim Number:

Policy Number:

Type of Loss:

Date of Loss:
Date Inspected:

Date Received:
Date Entered: 1/27/2026 6:13 AM

Price List: TXHO8X_JAN26
Restoration/Service/Remodel
Estimate: 4219_TEXANA_DR_

4219_TEXANA_DR_
Roof

DESCRIPTION	QUANTITY	UNIT PRICE	TAX	RCV	DEPREC.	ACV
1. Tear off, haul and dispose of comp. shingles - 3 tab	36.70 SQ	71.44	0.00	2,621.85	(0.00)	2,621.85
2. Remove Additional charge for steep roof - 7/12 to 9/12 slope	10.42 SQ	17.50	0.00	182.35	(0.00)	182.35
3. Remove Additional charge for steep roof - 10/12 - 12/12 slope	26.28 SQ	27.50	0.00	722.70	(0.00)	722.70
4. Ice & water barrier/Eaves*	1,494.00 SF	1.83	70.26	2,804.28	(0.00)	2,804.28
5. Ice & water barrier/Valleys*	321.00 SF	1.83	15.10	602.53	(0.00)	602.53
6. Roofing felt - 15 lb.	21.73 SQ	38.09	17.82	845.52	(0.00)	845.52
7. Asphalt starter - universal starter course	290.00 LF	1.90	14.12	565.12	(0.00)	565.12
8. Drip edge/gutter apron	249.00 LF	3.23	29.99	834.26	(0.00)	834.26
9. Drip edge	41.00 LF	2.95	3.99	124.94	(0.00)	124.94
10. Laminated - comp. shingle rfg. - w/out felt	42.33 SQ	269.30	472.36	11,871.83	(0.00)	11,871.83
11. Additional charge for steep roof - 7/12 to 9/12 slope	10.42 SQ	46.09	0.00	480.26	(0.00)	480.26
12. Additional charge for steep roof - 10/12 - 12/12 slope	26.28 SQ	72.47	0.00	1,904.51	(0.00)	1,904.51
13. R&R Gable cornice return - laminated	4.00 EA	104.22	2.83	419.71	(0.00)	419.71
14. Flashing - pipe jack - lead	6.00 EA	88.57	26.31	557.73	(0.00)	557.73
15. Step flashing	3.00 LF	11.20	0.55	34.15	(0.00)	34.15
16. R&R Counterflashing - Apron flashing	10.00 LF	12.00	1.72	121.72	(0.00)	121.72
17. Flashing - kick-out diverter	2.00 EA	29.32	2.13	60.77	(0.00)	60.77
18. R&R Chimney flashing - average (32" x 36")	1.00 EA	486.62	9.54	496.16	(0.00)	496.16
19. Exhaust cap - through roof - 6" to 8"	4.00 EA	108.11	16.98	449.42	(0.00)	449.42
20. Roof vent - turbine type	2.00 EA	159.65	17.00	336.30	(0.00)	336.30
21. Hip / Ridge cap - Standard profile - composition shingles	253.00 LF	6.17	58.23	1,619.24	(0.00)	1,619.24
22. Digital satellite system - Detach & reset	1.00 EA	45.75	0.00	45.75	(0.00)	45.75
Totals: Roof			758.93	27,701.10	0.00	27,701.10
Line Item Totals: 4219_TEXANA_DR_			758.93	27,701.10	0.00	27,701.10

Summary for Dwelling

Line Item Total	26,942.17
Material Sales Tax	758.93
Replacement Cost Value	\$27,701.10
Net Claim	\$27,701.10

ScopeConnect

Recap of Taxes

	Material Sales Tax (8.25%)	Cleaning Mtl Tax (8.25%)	Cleaning Sales Tax (8.25%)	Manuf. Home Tax (5%)	Storage Rental Tax (8.25%)	Total Tax (8.25%)
Line Items	758.93	0.00	0.00	0.00	0.00	0.00
Total	758.93	0.00	0.00	0.00	0.00	0.00

Recap by Room

Estimate: 4219_TEXANA_DR_ Roof	26,942.17	100.00%
Subtotal of Areas	26,942.17	100.00%
Total	26,942.17	100.00%

Recap by Category

Items	Total	%
GENERAL DEMOLITION	3,627.37	13.09%
ROOFING	23,314.80	84.17%
Subtotal	26,942.17	97.26%
Material Sales Tax	758.93	2.74%
Total	27,701.10	100.00%